## **Coldbay Installation (Remote Gear)**



## 220-240V / 50-60Hz IP65

Terminal Labelling:

L1 E 🖳 Switched Liv Earth Neutral

Emergency L2 DA/AT3 DA/AT3 Dimming

Unswitched Live DALI Autotest DALI Autotest

Dimming -/D1/DA +/D2/DA L3


Analogue/DSI/DALI Analogue/DSI/DALI Switch Dim / Corridor Function









WARNING: Luminaire must be earthed. Risk of electric shock from LED boards if operated with cover removed. Installation / operation outside of luminaires intended scope invalidates warranty. Suitable only for domestic / light industrial / industrial applications within the scope of EN55015. Tested to compliance with BSEN 60598: specification for general requirements and tests. Must be installed by a suitably qualified person in accordance with all relevant legislation. Ambient operating temperature of 0°C to 25°C. If maximum operating temperature is exceeded luminaire will automatically dim / switch off. Terminal blocks are rated to 16A unless stated otherwise. The light source contained in this luminaire shall only be replaced by the manufacturer itself or his service agent or a similar qualified person. LUMINAIRES WITH EMERGENCY PACK: When supply is isolated battery output terminals may be live if battery is connected. Isolate mains and battery before servicing. Emergency luminaires require unswitched live connection taken from same phase as switched supply. When unswitched supply is connected status indicator illuminates green, when unswitched supply is disconnected indicator extinguishes and luminaire operates in emergency mode. 24 hour charge period required before undertaking full discharge test. Emergency test sheets provided should be used to record all emergency tests. Batteries should be replaced when 3 hour duration is not met. Excessive switching of permanent live may result in premature battery failure. Battery electrolyte can be harmful to eyes / open wounds, do not puncture, if electrolyte touches skin / eyes flush with water. Do not incinerate batteries.








Connect the luminaire head cabling to the remote gear box. Ensure cable restraint is used.



4. Close attention should be payed to the labelling of the cables. Flex 1 and Flex 2 cables should be connected to respective terminal blocks.







## **Coldbay Installation (Remote Gear)**



